



TRAVANCORE TITANIUM PRODUCTS LIMITED  
Kochuveli, Thiruvananthapuram 695 021  
Phone : 0471 2502163 email: contract@ttpltd.in

TTP/CD/CN/KV-39/Thickness testing of acid storage tank/21-22

23.09.2021

## **Tender Notice**

### **“ Thickness testing of acid storage tank”**

Sealed tenders are invited from experienced Contractors in prescribed format for doing the “**Thickness testing of acid storage tanks**”. The tender shall be enclosed in an envelope, sealed and superscribed with Tender No., Date and due date and description as “**Thickness testing of acid storage tanks**”. The same shall then be forwarded to “**The Manager(Commercial), Travancore Titanium Products Limited, Kochuveli, Thiruvananthapuram, Kerala, Pin - 695 021.**”

The tender form can be obtained from the office of the undersigned between 9.00 a.m and 4.00 p.m on all working days except Saturdays, after remitting the tender form cost. **Cost of tender form is Rs.300/- + GST @ 18% (Total Rs.354/-)**. Tender document can also be downloaded from our website ([www.travancoretitanium.com](http://www.travancoretitanium.com)) and shall submit the Tender along with a DD against the tender form cost & EMD in favour of Travancore Titanium Products Limited payable at Thiruvananthapuram.

**EMD: Rs. 1,020/- (by cash /DD) (refundable)**

Sealed Tenders will be received at our office on all working days and the last date for submitting the same is on **08.10.2021** at 12 noon. Tenders received after the due date & time will not be accepted. Fax/email offers also will not be accepted. The bids will be opened on 2 pm on **08.10.2021** in the presence of the tenderers present at that time.

for TRAVANCORE TITANIUM PRODUCTS LIMITED

**Manager(Commercial)**

Encl: proforma

Signature of the bidder:

page 1 of 1



TRAVANCORE TITANIUM PRODUCTS LIMITED

Kochuvelli, Thiruvananthapuram 695 021

Phone : 0471 2502163 email: contract@tptltd.in

**Tender Notice**

TTP/CD/CN/KV-39/Thickness testing of acid storage tank/21-22

23.09.2021

**Name of work: Thickness testing of acid storage tanks**

**Due date : 08.10.2021 upto 12 noon (date of submission of tender)**

**Scope of Work**

Details of tank and points to be tested noted below:

Sl. No.	Material Description	Capacity	No. of points to be tested
1	Acid Storage Tank No. A, B, C, D,E,F	1600 MT (Height 10 metres, Dia – 10 metres)	600
2	Acid Storage Tank 3	200 MT (Height 3 metres, Dia – 6.7 metres)	60
3	Acid Storage Tank No, 2, 4 & 5	300 MT (Height 5 metres, Dia – 6.7 metres)	150
4	Leaching Tanks	9 MT (Height 1.5 metres, Dia – 2 metres)	40
5	Acid Measuring Tank	27 MT (Height 2.5 metres, dia 2.5 metre)	30
6	MS Acid Pumping lines	2 ½ “, 3”, 4 inch	60
7	Furnace Oil Pumping Line to Plant	4 inch	15

**Terms & Conditions**

1. Bidders should submit copies of following documents with their price bid
  - (a) Registration (class and type) with specified agencies and previous pre-qualification (s) for similar jobs.
  - (b) Experience on similar work (s) during last 2 year with copies of Work Order
  - (c) Contractor who has already undertaken same work in M/s.TTPL exempted from submitting the documents as stated in terms 1 (a) & 1 (b). All the other bidders should submit the respective documents.
2. Storage tanks height vary from 1.5 metres to 10 metres. Necessary scaffoldings to be provided at specified locations for thickness testing which is under the scope of Contractor. All other equipments, tools etc. are to be brought by the Contractor for testing.
3. The Contractor should test the thickness of acid storage tank shell & roof at locations specified by the Officer-in charge.

Signature of the bidder:

Page 1 of 5

4. After testing specified locations, the scrapped portion should be cleaned and repainted (2 coats) with red oxide primer. No extra amount will be given. Paint will be issued by M/s.TTPL at free of cost. The Contractor should clear the work site and convey the scrap material, if any, to the M/s.TTPL scrap yard after the completion of work by employing their own labour and equipment at their own risk and cost within the time stipulated in the work order.
5. Contractor shall arrange and depute adequate trained manpower to execute all work associated with testing activity viz., scaffold erecting and dismantling of scaffolds, painting etc. M/s.TTPL will not provide any manpower for such activity and no extra claim will be entertained on that account. Anything required beyond above including the manpower for material movement or similar work shall be arranged by the contractor at his cost and risk.
6. The Contractor should strictly abide by all the safety rules and regulations prevailing at M/s.TTPL. All the workmen of the Contractor should wear safety equipment while on work, especially when working at height. M/s.TTPL will not be responsible for any mishap during the tenure of the work. All safety equipments should be brought by the Contractor.
7. Testing & Certification charge: Unit rate per point (Sl. No.1 to 7) inclusive of labour charge, supervision charge and for issuance of certificate to be quoted in the price bid.
8. **Completion Period: Work should be started within 15 days from the date of issue of Work Order and completed within one month.**
9. Test certificates (4 copies – spiral bound) should be submitted within 20 days from the date of completion of work.
10. All questions, disputes or differences arising under, out of or in connection with this tender shall be decided by the Managing Director (MD) of the company and his decision shall be final and binding.
11. The company reserves the right to reject any or all tender or to accept any tender partly or wholly without assigning any reason.
12. The contractor will be responsible for meeting all statutory requirements of the various labour enactments enforceable in Kerala from time to time and should indemnify and keep indemnified the against all losses and damages sustained by the company on this regard at all times.
13. Payment will be made after completion of work satisfactorily and submission of the bill.
14. **Jurisdiction:** Any dispute or questions relating to or arising out of the finalization of this tender, if remains, shall be subject to the executive jurisdiction of the courts at Thiruvananthapuram.
15. **Validity of rates:** The quoted rate must be valid for a period for 90 days from the date of opening of the tender and till the completion of the work if the contract is awarded.
16. Bids should bear the signature of the bidder in all pages.
17. **Liquidated Damages for Delay in Delivery:** In case of any delay in the execution of the Order beyond the stipulated date of delivery/ delivery schedule including any extension permitted in writing, the TTPL reserves right to recover from the vendor a sum equivalent to 0.5% of the value of the delay materials/ equipment for each week of delay and part thereof subject to a maximum of 10% of the total value of the Order. Alternatively, the Purchaser reserves the right to purchase the material/ equipment from elsewhere at the sole risk and cost of the vendor and recover all such extra cost incurred by the purchaser in procuring the material by the above procedure.

18. **Tender Form Cost: Rs.300/- + 18% GST (Total Rs.354/-)**
19. **Earnest Money Deposit (EMD) : Rs.1020/-**
20. **Exemption in Tender Form Cost and EMD is as per Govt. rules.**
21. **Security Deposit** : An amount of 3% of the contract value shall be remitted by the successful bidder as Security Deposit (SD) within 7 days from the date of issue of Work Order. No interest will be payable for the SD amount. The failure to remit the SD in time will result in the rejection of the offer and forfeiture of EMD without any notice.
22. **Due date of submission of tender: 08.10.2021 upto 12.00 noon** and will be opened at **2.00 p.m.** on the same day in the presence of the those tenderers who are present at that time.
23. **Documents to be submitted along with the tender**
  1. **Tender Document duly filled and signed in all pages**
  2. **Proof of experience.**
  3. **Proof of Tender cost and EMD remittance**
  4. **Copy of ESI,PF,GST and MSME (if applicable) registration.**
24. **Evaluation of bids:** The evaluation of the bids will be based only on the documents submitted:
25. **Deductions:** All statutory deductions such as Income Tax, Kerala Constructions Workers' Welfare Funds, etc., will be made from the contractor's bill as per rules. The contractor shall remit ESI and PF amount and the proof of remittance shall be furnished when ever company insists.
26. Bids should bear the signature of the bidder in all pages.
27. All workers engaged with the work shall have Police Clearance Certificate (PCC) and other formalities insisted by Security Department of TTPL.
28. Canteen charges will be deducted from the contractors bill as fixed by the canteen authorities.
29. If the Contractor fails to remit SD and execute agreement within the stipulated period, Company have the right to cancel the work order awarded to the successful bidder and the work will either be executed by L2 bidder or any other source at the risk and cost of the successful bidder.
30. All statutory deductions will be made from the contractor's bill as per rules.
31. Bids without remitting EMD /Tender cost or both will be rejected.
32. Conditional tenders are not acceptable.

**for TRAVANCORE TITANIUM PRODUCTS LIMITED**



**Manager(Commercial)**

## **PARTICULARS OF TENDERER**

1. Name of the Bidder:
2. (a) Registered office address of the Bidder:  
  
(b) Address for correspondence:
3. Phone Nos.:
4. Mobile Nos.:
5. E-mail address:
6. Status of the tenderer (Individual, Prop. firm, Partnership, Ltd. Company, Co-operative Society, Other):
7. Registration No.:
8. Year of establishment:
9. PAN:
10. GST Registration No.
11. ESI Registration No.
12. PF Registration No.
13. MSME (if applicable) registration number:
14. Name and address of Proprietor/ Partners/ Directors:

### **Declaration**

I/ We here by accept all the above conditions in its entirety.

Signature        :

Name             :

Address         :

Place:

Date:

Signature of the bidder:

PROFORMA

My lowest rate for the above work mentioned in the Tender No. **TTP/CD/CN/KV-39/Thickness testing of acid storage tank/21-22** dated **23.09.21**

Sl. No.	Material Description	Capacity	No. of points to be tested	Rate per point (Rs.)	GST (Rs.)	Total (Rs.)
1	Acid Storage Tank No. A, B, C, D,E,F	1600 MT (Height 10 metres, Dia – 10 metres)	600			
2	Acid Storage Tank 3	200 MT (Height 3 metres, Dia – 6.7 metres)	60			
3	Acid Storage Tank No, 2, 4 & 5	300 MT (Height 5 metres, Dia – 6.7 metres)	150			
4	Leaching Tanks	9 MT (Height 1.5 metres, Dia – 2 metres)	40			
5	Acid Measuring Tank	27 MT (Height 3 metres, dia 2.5 metre)	30			
6	MS Acid Pumping lines	2 ½ “, 3”, 4 inch	60			
7	Furnace Oil Pumping line to tank	4 inch	15			

***\*\* Please mention whether the above rate is inclusive of GST or exclusive and specify the % of GST included or excluded***

GST Registration No. :

EMD Remittance details:

Signature of the Tenderer:

Name & Address. :

Phone no. :

Mobile No :

Fax No :

E Mail :

Signature of the bidder: