TRAVANCORE TITANIUM PRODUCTS LIMITED

Kochuveli, Thiruvananthapuram 695 021
Email: purchasettp@gmail.com

NOTICE INVITING TENDER

No.CD/CN/NC-06/Concrete_Footing_Substation/2026-27 **07.09.2026**

Sealed tenders are invited from experienced contractors in prescribed format for the work as per the schedule attached. The tender form can be had from the office of the undersigned between 10:00 am and 3.00 pm on all working days except Saturdays, on remitting the tender fee. Tender document can also be downloaded from our website www.travancoretitanium.com and shall submit the tender along with DD against the Tender Fee and EMD in favour of Travancore Titanium Products Limited payable at Thiruvananthapuram. The bids will be opened at the date and time given below in the presence of the tenderers present at that time.

The tender shall be enclosed in an envelope, sealed and superscribed with **"Tender No. & Date, Due Date and the Name of Work"**. The same shall then be forwarded to the **Head of Department (Commercial), Travancore Titanium Products Limited, Kochuveli, Thiruvananthapuram, Kerala, PIN - 695 021**.

Name of Work	:	Construction of concrete footing for the installation of GCB and CT at 66KV Substation
Tender Fee	:	Rs.500/- + GST @18% (Total Rs.590/-)
EMD	:	Rs.4,114/- (Refundable)

Sealed Tenders will be received at our office on all working days and the due date of submitting the same is on **29.09.2026 at 12.00 noon**. Tenders received after the due date and time will not be accepted. Fax/email offers also will not be accepted.

The bids will be opened at **2.00 pm on 29.09.2026** in the presence of the tenderers present at the time.

For TRAVANCORE TITANIUM PRODUCTS LTD

Head of Department (Commercial)

Encl: Tender document & attachments

Signature of the Tenderer:

TRAVANCORE TITANIUM PRODUCTS LIMITED
Kochuveli, Thiruvananthapuram 695 021
Email: purchasettp@gmail.com

TENDER

No.CD/CN/NC-06/Concrete_Footing_Substation/2026-27 07.09.2026

Name of work: Construction of concrete footing for the installation of GCB and CT at 66KV Substation
Due Date : 29.09.2026 (12 Noon)

1. **Scope of work**: Detailed in theattached Work Schedule
2. **Quantity** : Detailed in the attached Work Schedule
3. **Price** : To be filled up in the attached Price Proforma
4. **Period** : The work should be completed within **21 days**from the date of issue of Work Order
5. The quantities considered in the estimate are approximate and no extra claim is permissible.
6. The tenderer must have **valid ESI, PF and MSME registration,** if applicable, for participating in the tender.
   a. If the Bidder is not covered under PF Act, a Self Declaration is to be submitted along with the Tender.
   b. If the bidder is not covered under ESI Act, CAR (Contractors' All Risk) Policy for the workers has to be submitted for the entire period of contract. Declaration to be submitted along with the Tender.
7. **Pre Qualification Criteria**:
   i) Experience of having successfully completed similar works as per the scope of work like concrete works during the last seven years ending 31st August 2026. In support of this, the tenderer should submit the **copy of such work orders along with satisfactory completion certificates.**
   ii) The bidders with whom Government transactions have been banned/blacklisted/suspended due to any reason will not be eligible to participate in the tender. A self declaration as per **Annexure A** to be submitted along with the tender.
8. The contractor has to supply as many specialized workers and necessary tools and tackles based on the urgency of work as mentioned by the Engineer-in-charge and the work has to be completed within the time limit.
9. Approved brand of cement – Dalmia/Malabar/Shankar or any other as approved.
10. Approved brand of TMT bars – Tata/JSW/SAIL/Vizag or any other as approved.
11. Blue variety 20mm metal to be used for concrete works.
12. All the balance materials should be removed and cleared from the site as soon as the work is over.
13. The company is no way responsible for any loss or damage of the materials entered in TTPL campusby the contractor.
14. **Payment Terms:** Payment will be made upon submission of billafter satisfactory completion of the work,with the recommendationof the officer in charge.
15. Copy of the work order and extension (if any) must be enclosed with the bill submitted for payment.
16. TTPL reserves the right to accept/reject any of the tender after evaluation with or without assigning reason no matter whether a tenderer has quoted the lowest rate. All questions/disputes arising out of or in connection with this shall be decided by the Managing Director of the company and his decision thereof shall be final and binding to all tenderers.
17. **Bids should bear the signature of the bidder in all pages of the tender document and work schedule.**
18. **The tenderer should remit Earnest Money Deposit (EMD) and Tender Fee mentioned in this document by means of DD or can remit cash at TTP's Cash Counter (if the amount**

is below Rs.10,000/-) and enclose the proof obtained thereof (Cash Receipt) along with the tender. Other modes of remittance will not be accepted.

19. **Tenders without remitting EMD and Tender Fee will be rejected.Exemption of EMD is as per Government rules.**
20. **Conditional Bids shall not be considered.**
21. **The rate quoted shall be exclusive of GST and percentage of GST applicable should be mentioned at the space provided in the price proforma. If the bidder is below the threshold limit of GST that should be clearly mentioned at the space provided for GST Number.**
22. It is not binding on the company to accept the lowest offer. The company reserves the right to cancel/postpone the tender or to reject any or all offers without assigning any reason.
23. If any irregularity or fraudulent behavior is noticed on the part of the contractor/his agents/representatives or the crew of the vehicle engaged by the contractor for the performance of the contract, the company reserves the right to take all suitable action deemed fit against the contractor and those concerned.
24. The contractor will be responsible for meeting all the requirements of the various labour enactments applicable from time to time and should indemnify and keep indemnified the company against all losses and damages sustained by the company in this regard at all times.
25. Contractor should comply with all relevant formalities under Contract Labour (Regulation and Abolition) Act 1971, such as display of rate of wages, date, place and time of payment of wages, date of payment of unpaid wages etc. they should also intimate the time, date and place of disbursement of wages to the Supervisory Officer nominated under the above act for certification of payment to contract workers.
26. The contractor should strictly adhere to the Safety Rules prevailing in the company failing which penalty as decided will be imposed. It is entirely the contractor's responsibility to provide all safety equipments wherever necessary to their workmen. The Company is in no way responsible for any injury, disability or death of contractor's workmen due to non-compliance of safety regulations.
27. The successful bidder shall be held responsible for any penalty imposed on them on violation of statutory requirements/safety regulations and such penalties shall be met by the successful bidder themselves. The Workmen should follow the safety rules and regulations prevailing at TTPL from time to time. The contractor is liable to pay penalty of Rs.500/- for safety protocol violation/incident.
28. The Company reserves the right to cancel the work order forfeiting security deposit if the work is not started within 10 days from the date of receipt of work order and also to terminate the contract at any time if the work is not done with proportionate progress to the satisfaction of the company officials and in all such cases the company will be at liberty to get the work done in in any manner that the company deems fit and all losses and damage sustained by the company in this regard will be recovered from contractor and his assets.
29. Before starting the work, all the workmen under the contractor must undergo a safety training conducted by the Safety department. A declaration regarding successful completion of the training has to be submitted in HR Department.
30. **Validity of rates**: The quoted rate must be valid for a period for 90 days from the date of opening of the tender and till the completion of the work if the contract is awarded.
31. **Guarantee**: The tenderer should also provide a guarantee for six months against poor workmanship. 10% of the contract amount will be retained by the company during the guarantee period.
32. **Security Deposit:** The successful Tenderer should remit 5% of the contract value as security deposit as soon asthe work order is received and before commencement of thework. The security deposit will not carry any interest and will be refunded after completion of all contractual obligations.On default of the tenderer to remit the security deposit, the EMD amount will stand forfeited and if any loss or damage is sustained by the company in this regard, the same will also be recovered from the tenderer.
33. If the successful bidder fails to remit security deposit within the stipulated period, Company have the right to cancel the work order awarded to the successful bidder and the work will

either be executed by L2 bidder or any other source at the risk and cost of the successful bidder.

34. **Agreement:** The contractor should execute an agreement on stamp paper worth Rs.200/- if the contract value is above Rupees One Lakh, immediately from the date of remittance of Security Deposit and start work after remitting the SD.
35. **Jurisdiction:** Any legal proceeding or suit against the Company arising out of or in connection with the tender shall be filed or instituted in a court having jurisdiction in the city of Thiruvananthapuram, Kerala.
36. **Liquidated damages:** In case of any delay in the execution of the Order beyond the stipulated date of work schedule including any extension permitted in writing, the TTPL reserves right to recover from the contractor a sum equivalent to 0.5% of the total value of the delay for each week of delay and part thereof subject to a maximum of 10% of the total value of the Order. Alternatively, the Company reserves the right to execute the work from elsewhere at the sole risk and cost of the contractor and recover all such extra cost incurred by the company in execution of work by the above procedure.
37. All statutory deductions will be made from the contractor's bill as per rules.
38. All workers engaged with the work shall have Police Clearance Certificate (PCC) and other formalities insisted by the Security Department of TTPL.
39. In case of any matters pertaining to this tender which are not incorporated/specified therein, in such cases, guidelines of CVC/Kerala Store Purchase Manual shall be applicable.
40. **Estimate Amount: Rs.1,64,570/-**
41. **Tender Fee: Rs.500/- plus GST@18%(Total Rs.590/-)**
42. **EMD: Rs.4,114/- (Refundable)**
43. **Documents to be Submitted**:
    i.) Tender document and work schedule duly signed by the bidder in all pages
    ii.) Duly filled up and signed Price Proforma
    iii.) Proof of Tender Fee and EMD remittance
    iv.) Copy of GST,PF and ESI, MSME registration(if applicable)
    v.) Self Declaration as per Clause 6 (a) & (b) if applicable.
    vi.) Proof of experience as per clause 7
    vii.) Self declaration – **Annexure A as per Clause 8**
44. **Due Date: 25.09.2026 at 12 noon**

ForTRAVANCORE TITANIUM PRODUCTS LTD



Head of Department (Commercial)

PARTICULARS OF TENDERER

1. Name of the Bidder :

2. (a) Registered office address of the Bidder:

(b) Address for correspondence :

3. Mobile No. :

4. E-mail address :

5. Status of the Tenderer
(Individual, Prop. Firm, Partnership, Ltd. Company):

6. Registration No. :

7. Year of establishment :

8. Permanent Account No. (PAN issued by Income Tax Dept.):

9. GST Registration No. :

10. ESI Registration No. :

12. PF Registration No. :

13. MSME No. (if applicable) :

13. Name and address of Proprietor/Partners/Directors:

Declaration

I/We confirm that I/we have read and understood all tender conditions and I/we accept all tender conditions in its entirety.

Signature :

Name of Person signing :

Tenderer's Name and Address with seal :

Date :

WORK SCHEDULE
Estimation

Name of Work: **Construction of concrete footing for the installation of GCB and CT at 66KV Substation**

Tender No.**CD/CN/NC-06/Concrete_Footing_Substation/2026-27 dated 07.09.2026**

Sl. No.	Description	Unit	Rate (Rs.)	Qty	Amount (Rs.) excluding GST
1	Demolishing R.C.C. work by mechanical means and stockpiling at designated locations and disposal of dismantled materials up to a lead of 1 kilometer, stacking serviceable and unserviceable materials separately including cutting reinforcement bars	cum	2984.93	4.65	13869.18
2	Earth work in excavation by mechanical means (hydraulic excavator)/manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10sqm on plan) including getting out and disposal of excavated earth lead up to 50m and lift up to 1.5m as directed by Engineer-in-charge. All kinds of soil	cum	263.35	24.06	6335.41
3	Open timbering in trenches including strutting and shoring complete (measurements to be taken of the face area timbered): Depth not exceeding 1.5m	sqm	87.87	41.18	3618.84
4	Centering and shuttering including strutting, etc. and removal of form for: foundations, footings, bases of columns, etc for mass concrete	sqm	394.74	22.35	8823.23
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level. 1:2:4 [cement : 2 coarse sand (zone-III) derived from natural resources : 4 graded stone aggregate 20 mm nominal size derived from natural sources]	cum	9441.22	0.69	6470.07
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more	Kg	114.92	537.14	61727.76
7	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/ Ordinary Portland/Portland Slag Cement, admixtures in recommended proportions as per IS:9103 to accelerate/retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of	cum	11131.56	4.06	45149.61

	laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the Engineer-in-charge. All work up to plinth level concrete of M25 grade with minimum cement content of 400 Kg/cum				
8	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement – All work up to plinth level 1:1:5:3 (1 cement 1:5 coarse sand : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	10721.86	0.51	5468.15
9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering etc complete as per the direction of the Engineer-in-charge	cum	543.17	17.14	9307.73
10	Providing bolt hole of required size as per the direction of the Engineer-in-charge	Nos	190.00	20.00	3800.00
	Grand Total (One Lakh Sixty Four Thousand Five Hundred Seventy only)				**164570.00**

Dimension of the foundation

1) 1 No. of 66KV GCB foundation – RCC 800x2400x1000mm (WxLxD) and its appropriate PCC
2) 3 Nos. of 66KV CT foundation – RCC 900x900x800

Scope of work includes:

- Setting out and fixing bolts
- Construction of concrete footing as per the specified dimensions
- Concrete mixing shall be M25 grade or greater with steel dimension 16mm or greater
- Ensure all the works are carried out in accordance with relevant drawing of GCB and specification

PRICE PROFORMA

Name of Work:**Construction of concrete footing for the installation of GCB and CT at 66KV Substation**

Tender No.**CD/CN/NC-06/Concrete_Footing_Substation/2026-27 dated 07.09.2026**

I/we have read and understood all the tender conditions and work schedule of the tender in its entirety and offer my/our lowest rates to carry out the work as per the tender below:

Sl. No.	Description	Unit	Qty	Rate (Rs)	Amount (Rs) excluding GST	GST (%)
1	Demolishing R.C.C. work by mechanical means and stockpiling at designated locations and disposal of dismantled materials up to a lead of 1 kilometer, stacking serviceable and unserviceable materials separately including cutting reinforcement bars	cum	4.65			
2	Earth work in excavation by mechanica means (hydraulic excavator)/manual means over areas (exceeding 30cm in depth, 1.5m in width as well as 10sqm on plan) including getting out and disposal of excavated earth lead up to 50m and lift up to 1.5m as directed by Engineer-in-charge. All kinds of soil	cum	24.06			
3	Open timbering in trenches including strutting and shoring complete (measurements to be taken of the face area timbered): Depth not exceeding 1.5m	sqm	41.18			
4	Centering and shuttering including strutting, etc. and removal of form for: foundations, footings, bases of columns etc for mass concrete	sqm	22.35			
5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering – All work up to plinth level. 1:2:4 [cement : 2 coarse sand (zone-III) derived from natural resources : 4 graded stone aggregate 20 mm nominal size derived from natural sources]	cum	0.69			
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete up to plinth level Thermo-Mechanically Treated bars of grade Fe-500D or more	Kg	537.14			
7	Providing and laying in position ready mixed or site batched design mix cement concrete for reinforced cement concrete work; using coarse aggregate and fine aggregate derived from natural sources, Portland Pozzolana/ Ordinary					

	Portland/Portland Slag Cement, admixtures in recommended proportions as per IS:9103 to accelerate/retard setting of concrete, to improve durability and workability without impairing strength; including pumping of concrete to site of laying, curing, carriage for all leads; but excluding the cost of centering, shuttering, finishing and reinforcement as per direction of the Engineer-in-charge. All work up to plinth level concrete of M25 grade with minimum cement content of 400 Kg/cum	cum	4.06			
8	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement – All work up to plinth level 1:1:5:3 (1 cement 1:5 coarse sand 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	0.51			
9	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering etc complete as per the direction of the Engineer-in-charge	cum	17.14			
10	Providing bolt hole of required size as per the direction of the Engineer-in-charge	Nos	20.00			
	GRAND TOTAL					

Please mention % of GST at the space provided. If not mentioned, the rate will be considered asinclusive of GST. Also if the bidder is within the threshold limit of GST the same shall be mentioned at the space.

Whether below threshold limit :

Tender cost remittance details :

EMD Remittance details :

Signature of the Bidder :

Name & Address :

Date:

Mobile No: Email:

ANNEXURE A

SELF DECLARATION

Date:

From

_____

_____

_____

To

The Head of Department (Commercial)
Travancore Titanium Products Limited
Kochuveli, Thiruvananthapuram
Kerala – 695 021

Sir,

Name of Work: **Construction of concrete footing for the installation of GCB and CT at 66KV Substation**

Tender No. **CD/CN/NC-06/Concrete_Footing_Substation/2026-27 dated 07.09.2026**

---

1. I/We have carefully studied the terms and conditions of the tender vide your **Tender No.CD/CN/NC-06/Concrete_Footing_Substation/2026-27 dated 07.09.2026**.
2. I/We hereby certify that I/we have never been banned/black listed/suspended by any of the State/UT/Central Government/PSU organizations.
3. In the event of any such information pertaining to the aforesaid matter is found at any given point of time, either during the course of the contract or at the bidding stage, my/our bid/contract shall be liable for truncation/cancellation/termination without any notice at the sole discretion of the company.

Yours faithfully,

Signature and Address of the Bidder